

Anthony Esson, Architect
PO Box 479
Gaylord, Michigan 49734

West Branch Rose City Area Schools
Surline Elementary/Middle School Lighting Improvements
West Branch, Michigan

January 13, 2021

Project No. 263-18H

ADDENDUM NO. 1

This Addendum is being issued for the purpose of modifying and/or clarifying the original Bidding Documents dated November 8, 2020 and shall take precedence over them.

All work included herein shall be in accordance with the general requirements of the original bidding documents, except as specifically noted herein.

Supplemental Documents Issued: Revised Sheet T dated November 8, 2020

- Item No. 1: Refer to Revised Sheet T which has been revised to correct various misidentifications and typos.
- Item No. 2: Refer to Sheet E1.4; Classroom 164: Disregard reference to a WAC in Classroom 164.
- Item No. 3: Ceiling Panel Materials: Ceiling panels for infill of ceilings where light fixtures numbers were reduced, or for patching where pendent fixtures were removed shall be USG Ceilings Fifth Avenue 2x4 Lay-in Ceiling Panels, no substitutions.

END OF ADDENDUM NO. 1

WEST BRANCH - ROSE CITY AREA SCHOOLS

SURLINE ELEMENTARY/MIDDLE SCHOOL LIGHTING IMPROVEMENTS

WEST BRANCH, MICHIGAN



ANTHONY P. ESSON
ARCHITECT
PO BOX 478
GAYLORD, MICHIGAN
TELEPHONE: (889) 732-9585

DRAWING TITLE
TITLE SHEET
PROJECT INFORMATION

PROJECT TITLE
WEST BRANCH ROSE CITY AREA SCHOOLS
SF1.3 - SURLINE ELEMENTARY/MIDDLE SCHOOL LIGHTING IMPROVEMENTS
WEST BRANCH, MICHIGAN

PROJECT NO.
263-18H

DATE
MARCH 20, 2020
NOV. 18, 2020

SHEET
T

STATE OF MICHIGAN
REGISTRATION

PROJECT DESCRIPTION
SURLINE ELEMENTARY/MIDDLE LIGHTING IMPROVEMENTS
<small>IN GENERAL, WORK OF THE CONTRACT INCLUDES: 1. RETROFIT LIGHTING FIXTURES FOR LED IN DESIGNATED ROOMS. 2. REPLACE EXISTING LIGHT FIXTURES IN DESIGNATED ROOMS. 3. PROVIDE PERMANENT ELECTRICAL RECEPTACLES FOR PROJECTION EQUIPMENT IN DESIGNATED ROOMS.</small>

BUILDING DATA
SURLINE ELEMENTARY/MIDDLE LIGHTING IMPROVEMENTS
<small>APPLICABLE CODES 2015 MICHIGAN CODE SERIES 2012 NFPA 101 LIFE SAFETY CODE USE AND OCCUPANCY CLASSIFICATION USE GROUP E - EDUCATIONAL CONSTRUCTION TYPE MSG CONSTRUCTION TYPE IIB NFPA 101 CONSTRUCTION TYPE II(000) BUILDING AREA 155,246 sf WORK AREA LIGHTING REPLACEMENT - 36,778 sf FIRE SUPPRESSION NONE OCCUPANT LOAD (ACTUAL) STUDENTS: 1357 STAFF: 151</small>

SHEET INDEX
SURLINE ELEMENTARY/MIDDLE LIGHTING IMPROVEMENTS
<small>T TITLE SHEET / PROJECT INFORMATION A0.1 COMPOSITE FLOOR PLAN E1.1 FLOOR PLAN PART "A" - ELECTRICAL E1.2 FLOOR PLAN PART "B" - ELECTRICAL E1.3 FLOOR PLAN PART "C" - ELECTRICAL E1.4 FLOOR PLAN PART "D" - ELECTRICAL E1.5 FLOOR PLAN PART "E" - ELECTRICAL E1.6 FLOOR PLAN PART "F" - ELECTRICAL E1.7 FLOOR PLAN PART "G" - ELECTRICAL E1.8 FLOOR PLAN PART "H" - ELECTRICAL</small>