

Anthony Esson, Architect  
PO Box 479  
Gaylord, Michigan 49734

Central Lake Public Schools  
Elementary Secure Entrance  
Central Lake, Michigan

May 6, 2019

Project No. 267-18B

### ADDENDUM NO. 1

This Addendum is being issued for the purpose of modifying and/or clarifying the original Bidding Documents dated April 18, 2019 and shall take precedence over them.

All work included herein shall be in accordance with the general requirements of the original bidding documents, except as specifically noted herein.

This Addendum is being sent to all known plan holders, suppliers, plan rooms, and governmental agencies having received Bidding Documents.

Supplemental Documents Issued:           None:

- Item No. 1:       Refer to Curb and Walk Notes on Sheet C1.2: Disregard reference in Note 2 to a snow melt system. There is currently no snowmelt system, nor is one being added.
- Item No. 2:       Refer to Partition Schedule on Sheet A1.1: Note that the partition assemblies are listed in order from top to bottom. P1 is the top listed assembly, and P2 is the bottom listed assembly. Also note that partitions are to be constructed to a total height of 9'-4". Bullet resistant panels and gypsum board is to be extended to the top of the partitions (9'-4").
- Item No. 3:       Refer to Keyed Mechanical Note 1 on Sheet ME1.1: Note that the existing hot water heating line to the existing baseboard is located in the existing masonry wall at the north end of Vestibule 105, but that it is accessible above the ceiling. The new feed required to the shortened baseboard can be run above the ceiling across Vestibule 105, and dropped down in the new partition between Vestibule 105 and Office 106.
- Item No.4:       Refer to Main Entrance Electrical Plan on Sheet ME1.1:
- a.       Note that an access control reader will be installed at Door 101.1. Access control components that are to be included in the contact are listed in Hardware Set 1.
  - b.       Note that an access control reader will be installed at Door 102.1. Access control components that are to be included in the contact are listed in Hardware Set 2.
  - c.       Note that an access control reader will be installed at Door 102.2. Access control components that are to be included in the contact are listed in Hardware Set 3.
  - d.       Note that an access control reader will be installed at Door 105.1. Access control components that are to be included in the contact are listed in Hardware Set 4.

**END OF ADDENDUM NO. 1**